Tabulation of Bids

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(1) CONSTRUCTION RESOURCE GROUP, INC.		(2) LCI-LINEBERGER CONSTRUCTION, INC.		(3) GRANITE CONTRACTING, LLC	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 1	PayItems For ProjectId: P028571	**Cat Alt Set:**				**Cat Alt Member:**	
0010 1031000 MOBILIZATION	(1) LS	3,700.00000	3,700.00	10,500.00000	10,500.00	4,800.00000	4,800.00
0020 1032010 BONDS AND INSURANCE	(1) LS	1,500.00000	1,500.00	1,650.00000	1,650.00	1,900.00000	1,900.00
0030 1071000 TRAFFIC CONTROL	(1) LS	2,500.00000	2,500.00	1,950.00000	1,950.00	15,000.00000	15,000.00
0040 2025000 REMOVAL & DISPOSAL OF EXISTING ASPHALT PAVEMENT	225.000 SY	15.00000	3,375.00	17.75000	3,993.75	15.00000	3,375.00
0050 2031000 UNCLASSIFIED EXCAVATION	350.000 CY	15.00000	5,250.00	20.00000	7,000.00	42.00000	14,700.00
0060 2033000 BORROW EXCAVATION	310.000 CY	20.00000	6,200.00	50.00000	15,500.00	39.00000	12,090.00

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(1) CONSTRUCTION RESOURCE GROUP, INC.		(2) LCI-LINEBERGER CONSTRUCTION, INC.		(3) GRANITE CONTRACTING, LLC	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 1 PayItems For ProjectId: P028571		**Cat Alt Set:**				**Cat Alt Member:**	
0070 2081001 FINE GRADING	225.000 SY	8.00000	1,800.00	6.75000	1,518.75	16.00000	3,600.00
0080 4011004 LIQUID ASPHALT BINDER PG64-22	2.400 TON	900.00000	2,160.00	550.00000	1,320.00	607.00000	1,456.80
0090 4030340 HOT MIX ASPHALT SURFACE COURSE TYPE C	40.000 TON	180.00000	7,200.00	195.00000	7,800.00	162.00000	6,480.00
0100 6041200 BARRICADE - TYPE 3	84.000 LF	60.00000	5,040.00	37.00000	3,108.00	17.00000	1,428.00
0110 6051120 PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	206.000 SF	20.00000	4,120.00	8.00000	1,648.00	5.75000	1,184.50

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	(1) CONSTRUCTION RESOURCE GROUP, INC.		(2) LCI-LINEBERGER CONSTRUCTION, INC.		(3) GRANITE CONTRACTING, LLC	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 1 PayItems For ProjectId: P028571		**Cat Alt Set:**				**Cat Alt Member:**	
0120 6051125	70.000	20.00000	1,400.00	8.00000	560.00	5.75000	402.50
PERMANENT CONSTRUCTION SIGNS (BARRICADE MOUNTED)	SF						
0130 608100B	16.000	100.00000	1,600.00	75.00000	1,200.00	100.00000	1,600.00
TYPE B - FLASHING LIGHT	EA						
0140 6250010	200.000	1.00000	200.00	1.25000	250.00	1.00000	200.00
4" WHITE SOLID LINES (PVT. EDGE LINES)-FAST DRY PAINT	LF						
0150 6250110	200.000	1.00000	200.00	1.25000	250.00	1.00000	200.00
4"YELLOW SOLID LINE(PVT.EDGE&NO PASSING ZONE)-FAST DRY PAINT	LF						
0160 6271010	200.000	5.00000	1,000.00	2.50000	500.00	2.00000	400.00
4" WHITE SOLID LINES (PVT. EDGE LINES) THERMO.- 90 MIL.	LF						

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(1) CONSTRUCTION RESOURCE GROUP, INC.		(2) LCI-LINEBERGER CONSTRUCTION, INC.		(3) GRANITE CONTRACTING, LLC	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 1	PayItems For ProjectId: P028571	**Cat Alt Set:**				**Cat Alt Member:**	
0170 6271074 4" YELLOW SOLID LINES(PVT.EDGE LINES) THERMO-90 MIL.	200.000 LF	5.00000	1,000.00	2.50000	500.00	2.00000	400.00
0180 6301100 PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	2.000 EA	15.00000	30.00	30.00000	60.00	25.00000	50.00
0190 714111A 60" RC PIPE CUL.-CLASS III	60.000 LF	350.00000	21,000.00	425.00000	25,500.00	330.00000	19,800.00
0200 8041020 RIP-RAP (CLASS B)	40.000 TON	60.00000	2,400.00	85.00000	3,400.00	80.00000	3,200.00
0210 8048100 GEOTEXTILE FOR EROSION CONTROL UNDER RIPRAP(CLASS 1)TYPE A	25.000 SY	20.00000	500.00	3.00000	75.00	12.00000	300.00

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	(1) CONSTRUCTION RESOURCE GROUP, INC.		(2) LCI-LINEBERGER CONSTRUCTION, INC.		(3) GRANITE CONTRACTING, LLC	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 1 PayItems For ProjectId: P028571		**Cat Alt Set:**				**Cat Alt Member:**	
0220 8100101	0.100	2,500.00000	250.00	15,000.00000	1,500.00	10,000.00000	1,000.00
PERMANENT GRASSING FOR SMALL PROJECTS	ACRE						
0230 8151101	0.200	4,000.00000	800.00	3,000.00000	600.00	3,500.00000	700.00
TURF REINFORCEMENT MATTING (TRM) TYPE 1	MSY						
0240 8153000	500.000	3.00000	1,500.00	3.25000	1,625.00	2.00000	1,000.00
SILT FENCE	LF						
0250 8153090	100.000	3.00000	300.00	4.00000	400.00	3.00000	300.00
REPLACE/REPAIR SILT FENCE	LF						
0260 8154050	100.000	2.00000	200.00	4.00000	400.00	10.00000	1,000.00
REMOVAL OF SILT RETAINED BY SILT FENCE	LF						

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description		(4) EAGLE CONSTRUCTION COMPANY					
Alt Set / Alt Member	Quantity and Units	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
Section Totals:			$75,225.00		$92,808.50		$96,566.80
	Contract Totals		**$75,225.00**		**$92,808.50**		**$96,566.80**
	Cost Plus Time Totals		**$75,225.00**		**$92,808.50**		**96,566.80**

( ) indicates item is bid as Lump Sum

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(4) EAGLE CONSTRUCTION COMPANY Unit Price	 Ext Amount	 Unit Price	 Ext Amount	 Unit Price	 Ext Amount
SECTION: 1	PayItems For ProjectId: P028571	**Cat Alt Set:**			**Cat Alt Member:**		
0010 1031000 MOBILIZATION	(1) LS	46,000.00000	46,000.00				
0020 1032010 BONDS AND INSURANCE	(1) LS	1,800.00000	1,800.00				
0030 1071000 TRAFFIC CONTROL	(1) LS	15,500.00000	15,500.00				
0040 2025000 REMOVAL & DISPOSAL OF EXISTING ASPHALT PAVEMENT	225.000 SY	12.00000	2,700.00				
0050 2031000 UNCLASSIFIED EXCAVATION	350.000 CY	25.00000	8,750.00				
0060 2033000 BORROW EXCAVATION	310.000 CY	30.00000	9,300.00				

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(4) EAGLE CONSTRUCTION COMPANY Unit Price	 Ext Amount	 Unit Price	 Ext Amount	 Unit Price	 Ext Amount
SECTION: 1	PayItems For ProjectId: P028571	**Cat Alt Set:**			**Cat Alt Member:**		
0070 2081001 FINE GRADING	225.000 SY	5.00000	1,125.00				
0080 4011004 LIQUID ASPHALT BINDER PG64-22	2.400 TON	1,500.00000	3,600.00				
0090 4030340 HOT MIX ASPHALT SURFACE COURSE TYPE C	40.000 TON	250.00000	10,000.00				
0100 6041200 BARRICADE - TYPE 3	84.000 LF	30.00000	2,520.00				
0110 6051120 PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	206.000 SF	12.00000	2,472.00				

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(4) EAGLE CONSTRUCTION COMPANY Unit Price	 Ext Amount	 Unit Price	 Ext Amount	 Unit Price	 Ext Amount
SECTION: 1	PayItems For ProjectId: P028571	**Cat Alt Set:**				**Cat Alt Member:**	
0120 6051125	70.000	15.00000	1,050.00				
PERMANENT CONSTRUCTION SIGNS (BARRICADE MOUNTED)	SF						
0130 608100B	16.000	120.00000	1,920.00				
TYPE B - FLASHING LIGHT	EA						
0140 6250010	200.000	1.25000	250.00				
4" WHITE SOLID LINES (PVT. EDGE LINES)-FAST DRY PAINT	LF						
0150 6250110	200.000	1.25000	250.00				
4"YELLOW SOLID LINE(PVT.EDGE&NO PASSING ZONE)-FAST DRY PAINT	LF						
0160 6271010	200.000	2.50000	500.00				
4" WHITE SOLID LINES (PVT. EDGE LINES) THERMO.- 90 MIL.	LF						

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(4) EAGLE CONSTRUCTION COMPANY Unit Price	 Ext Amount	 Unit Price	 Ext Amount	 Unit Price	 Ext Amount
SECTION: 1	PayItems For ProjectId: P028571	**Cat Alt Set:**			**Cat Alt Member:**		
0170 6271074 4" YELLOW SOLID LINES(PVT.EDGE LINES) THERMO-90 MIL.	200.000 LF	2.50000	500.00				
0180 6301100 PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	2.000 EA	35.00000	70.00				
0190 714111A 60" RC PIPE CUL.-CLASS III	60.000 LF	640.00000	38,400.00				
0200 8041020 RIP-RAP (CLASS B)	40.000 TON	65.00000	2,600.00				
0210 8048100 GEOTEXTILE FOR EROSION CONTROL UNDER RIPRAP(CLASS 1)TYPE A	25.000 SY	20.00000	500.00				

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	(4) EAGLE CONSTRUCTION COMPANY Unit Price	(4) EAGLE CONSTRUCTION COMPANY Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 1 PayItems For ProjectId: P028571				**Cat Alt Set:**		**Cat Alt Member:**	
0220 8100101	0.100	10,000.00000	1,000.00				
PERMANENT GRASSING FOR SMALL PROJECTS	ACRE						
0230 8151101	0.200	7,000.00000	1,400.00				
TURF REINFORCEMENT MATTING (TRM) TYPE 1	MSY						
0240 8153000	500.000	3.75000	1,875.00				
SILT FENCE	LF						
0250 8153090	100.000	10.00000	1,000.00				
REPLACE/REPAIR SILT FENCE	LF						
0260 8154050	100.000	8.00000	800.00				
REMOVAL OF SILT RETAINED BY SILT FENCE	LF						

Contract ID: 4691450 **Counties:** York

Letting Date: October 13, 2015 **District(s):** 4

Call Order: 200 **Project(s):** P028571

Contract Time: 04/30/16 COMPLETION DATE **Min:** **Max:**

Contract Description: Pipe Replacement in York County

Line No / Item ID Item Description		(4) EAGLE CONSTRUCTION COMPANY					
Alt Set / Alt Member	Quantity and Units	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
Section Totals:			$155,882.00				
	Contract Totals		**$155,882.00**				
	Cost Plus Time Totals		**$155,882.00**				

( ) indicates item is bid as Lump Sum

Call Order: 200 **Contract ID:** 4691450 **Counties:** York

Letting Date: October 13, 2015 2:00 P.M. **District(s):** 4

Contract Time: 04/30/16 COMPLETION DATE

Contract Description: Pipe Replacement in York County **PCN(s):** P028571

Rank	Vendor ID/Name		Total Bid	Percent Of Low Bid
1	1CO090	CONSTRUCTION RESOURCE GROUP, INC.	$75,225.00	100.00%
2	1LC001	LCI-LINEBERGER CONSTRUCTION, INC.	$92,808.50	123.37%
3	1GR028	GRANITE CONTRACTING, LLC	$96,566.80	128.37%
4	1EA001	EAGLE CONSTRUCTION COMPANY	$155,882.00	207.22%

THIS IS TO CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF ALL THE BIDS RECEIVED ON THE ABOVE LETTING DATE FOR THIS PROJECT.

CONTRACT ADMINISTRATION ENGINEER_____ Date_____

Christy A. Hall
TITLE: Interim Secretary of Transportation